

BRUHATH BANGALORE MAHANAGARA PALIKE, DASARAHALLI ZONE
Office of the Executive Engineer Dasarahalli Division,
Schedule-B

NAME OF WORK: Emergency works in ward no.13 Mallasandra Shettyhalli sub division

Sl. No	Description of work	Unit	Qty	Rate quoted by the Contractor MUNIRAJA NAIK	
				In Figures (Rs.)	Amount
1	2	3	4	5	7
1	Earthwork excavation by manual means for roads, drains & similar works in ordinary soil involving , excavated surface leveled & sides neatly dressed , the disposed earth to be levelled neatly after breaking of clods complete as per specification	Cum	1144.80	192.85	220774.68
2	Providing and laying Plain cement concrete of mix 1:3:6 with OPC @ 220kgs, with crushed 40mm and down size graded granite metal coarse aggregates @0.89cum and fine aggregates @ 0.46cum, in foundation mechanically mixed, placed in foundation and compacted by vibration including curing for 14 days including cost of all materials, labour, HOM curing, form works, scaffolding and centering complete as per specifications:	Cum	18.00	4820.66	86771.88
3	Providing and laying plain/reinforced cement concrete for side drains using M20 nominal mix concrete with OPC at 300 kgs. with 20mm and down size granite metal coarse aggregates at 0.69 cum and fine aggregates at 0.43 cum machine mixed, well compacted for walls and bottom including centering, shuttering, cost of materials, HOM of machinery, curing etc., complete excluding cost of steel as per MORTH specification No. 1500, 1700, 2200. including cost of materials, labour, HOM complete as per specificationsdo- Wall & bottom thickness 15cm	Cum	54.00	6290.74	339699.96
4	Providing T.M.T steel reinforcement for R.C.C workincluding straightening, cutting, bending, hooking, placing in position,lapping and / or welding wherever required, tying with binding wire andanchoring to the adjoining members wherever necessary complete as per design (laps, hooks and wastage shall not be measured and paid)cost of materials, labour, HOM of machinery complete as per specifications	Tonne	3.89	63286.11	246182.97

Muniraj N

Signature of the Contractor

[Signature]
Executive Engineer
Dasarahalli Division
BBMP

5	Providing and fixing Precast RCC slab of 250mm thick for Culverts made of Plain/Reinforced Cement Concrete design mix M25 with OPC@340kgs,with 20mm and down size graded granite metal coarse aggregates @0.70cum and fine aggregates@0.47cum,with superplasticizer@3lts confirming to 189103-1999 Reaffirmed-2008,Open Foundation complete as per Drawing and Technical Specification including cost of all materials, labour,HOM curing,form works,scaffolding and centering complete as per specifications and pointing for l joints 1:3 cement mortar including form work,lift charges,curing and concrete finished surfaces on both sides etc,complete and as per the directions of Engineer in-Charge. (Data Rate)	Sqm	72.00	3214.75	23146.32
6	Providing and fixing Precast RCC cover slabs of 100 mm thick for drain in cement concrete 1:1.5:3 using graded granite jelly 20mm and down size with steel reinforcement and pointing for joints 1:3 cement mortar including form work, lift charges,curing and concrete finished surface on both sides etc,and complete as per the directions of Enginner in charges.(Data Rate)	Sqm	261.00	1413.12	368824.32

Signature of the Contractor

[Handwritten Signature]

Executive Engineer,
Dasarahalli Division,

[Handwritten Signature]

Signature of the Contractor

Executive Engineer
Dasarahalli Division
BBMP

in/epro